Serial No.	Description of work	Unit of work	Quantity
	SANITARY CONVENIENCES.		
23	Fixing Hindustani Closets with fittings, complete	No.	4
24	Fixing English do do ..	,,	1
25	Fixing single person basin urinals do	,,	2
26	Fixing one set of three persons range urinals with Cuddapah slab fittings, etc., complete.	,,	1
27	Fixing Lavatory with fittings, complete	,,	1
28	Fixing zinc cowel	,,	1
29	Constructing 6" x 4" gully trap cistern including fixing C. I. frame grating, complete.	,,	1
30	Constructing field's flushing tank of 50 gallons capacity not including the cost of the flushing syphon	,,	1
31	Laying and jointing 4" S. W. channel pipes including cutting and fixing in cement.	R.ft.	14
32	Laying and jointing 6" S. W. pipes including cutting and fixing in cement ..	,,	20
33	Do 4" do do ..	,,	10
34	Fixing 6" x 4" S. W. junction with cement	No.	6
35	Fixing 1½" lead pipes lavatory including making joints, etc., complete ..	R.ft.	6
36	Fixing 4" Wrought iron Ventilating Shaft of 16 feet height including cost of making connection to the drain and constructing a masonry support, cement plastered alround.	No.	1
	LAYING PIPE SEWERS FOR THE LATRINE.		
37	Earthwork excavation and refilling, watering, tamping and forming for the pipe line, complete.	C.yds.	554
38	Soft rock excavation do do ..	,,	277
39	Hard rock do do do ..	,,	277
40	Laying and jointing 6" S. W. pipes with cement	R.ft.	1,788
41	Fixing 6" S. W. bend and junction	No.	2
42	Laying and jointing 6" S. W. channel pipes in manholes with cement joints including cutting, etc., complete.	R.ft.	32
43	Constructing Manholes of size 4' x 4' with brick in surki mortar walls, 9" thick and a surki concrete bed 5½' x 5½' including the foundation of walls and surki concrete sloping sides on both sides of the open channel in the manhole, plastering with cement mortar (1 to 3) ½" thick to the bed and sides of manhole up to the top including rounding of edges and corners in cement mortar, fixing 6" burnt stone covering slabs (5½' x 5½') cutting groove in the slab and fixing manhole cover and frame in cement and fixing C. I. steps in the manhole where necessary (including cost of materials except cast iron manhole frame and cover and cast iron steps) of the following depths :—		
	3' deep	No.	1
	3½' ,, ...	,,	1
	4' ,, ...	,,	2
	4½' ,, ...	,,	2
	7' ,, ...	,,	1
	7½' ,, ...	,,	1
44	Repairing road crossing after refilling the trench including metalling and consolidation and barricading for 30 R. ft.	,,	1

H. F. MARKER,
Executive Engineer,
Special Water-Supply Construction Division.

BHADRAVATI DIVISION.

TIMBER SALE.

Abstract Notification.

The attention of the public is invited to the detailed notification regarding the auction sale of timber in the Bhadravati and Tarikere Depots of this Division on 6th April 1925 and 8th April 1925, respectively, published on pages 201, 202, Part VI of the *Mysore Gazette* dated 12th March 1925.

M. MACHAIYA,
District Forest Officer.

OFFICE OF THE EXECUTIVE ENGINEER, MYSORE DIVISION.

Notification dated Mysore, 11th March 1925.

It is hereby notified for the information of the public that the 2nd class travellers' bungalow at Mandya, will temporarily be closed for occupation by the intending travellers for two months with effect from the 20th March 1925, when it will be under repairs.

The date of reopening of the same for occupation by the public will duly be notified.

L. A. H. WINCKLER,
Executive Engineer.